

## OFFICE USE ONLY APPLICATION FOR OSHPD SPECIAL SEISMIC **CERTIFICATION PREAPPROVAL (OSP) APPLICATION #:** OSP - 0571 - 10 **OSHPD Special Seismic Certification Preapproval (OSP)** New □ Renewal **Manufacturer Information** Vertiv Corporation Manufacturer: Manufacturer's Technical Representative: Keith Goshia Mailing Address: 975 Pittsburgh Drive, Delaware, OH 43015 Telephone: (740) 833- 8557 Email: keith.goshia@vertivco.com **Product Information** Product Name: Vertiv eXL S1 UPS Product Type: Uninterruptible Power Supply (UPS Product Model Number: See Attachment A (List all unique product identification numbers and/or part numbers) Three phase UPS system with I/O Cabinets General Description: Mounting Description: Base mounted - rigid **Applicant Information** Applicant Company Name: TRU Compliance, by Structural Integrity Associates, Inc. Contact Person: Andrew M. Coughlin, SE Mailing Address: 5215 Hellyer Ave., Suite 210, San Jose, CA 95138 Telephone: 844-878-0200 Email: acoughlin@structint.com I hereby agree to reimburse the Office of Statewide Health Planning and Development review fees in accordance with the California Administrative Code. 2016. Signature of Applicant: Date: 5/29/2018 Title: Director, TRU Compliance Company Name: TRU Compliance, by Structural Integrity Associates, Inc.

"Access to Safe, Quality Healthcare Environments that Meet California's Diverse and Dynamic Needs'





Page 1 of 3

California Licensed Structural Engineer Responsible for the Engineering and Test Report(s)							
Company Name: _TRU Compliance, by Structural Integrity Associates, Inc.							
Name: Andrew M. Coughlin, SE California License Number: S6082							
Mailing Address: 215 Hellyer Ave., Suite 210, San Jose, CA 95138							
Telephone: 844-878-0200 Email: acoughlin@structint.com							
Supports and Attachments Preapproval							
Supports and attachments are preapproved under OPM- (Separate application for OSHPD Preapproval of Manufacturer's Certification (OPM) of Supports and attachments is required)							
Supports and attachments are not preapproved							
Certification Method							
BY:Ali Sumer							
Testing Laboratory  DATE: 03/20/2019							
Company Name: Pacific Earthquake Engineering Research (PEER)							
Contact Name: Alex Mead							
Mailing Address: 1301 South 46th St., Bldg.420, Richmond, CA 94804							
Telephone: 510-642-6475 Email: peer_center@berkeley.edu							



Page 2 of 7

03/20/2019



# OFFICE OF STATEWIDE HEALTH PLANNING AND DEVELOPMENT FACILITIES DEVELOPMENT DIVISION

Seismic Parameters								
Design in accordance with ASCE 7-10 Chapter 13: ⊠ Yes ☐ No								
Design Basis of Equipment or Components $(F_p/W_p) = 0.72 (z/h = 1); 0.64 (z/h = 0)$								
S <sub>DS</sub> (Design spectral response acceleration at short period, g) = 1.00 (z/h = 1); 1.43 (z/h = 0)								
a <sub>p</sub> (In-structure equipment or component amplification factor) = 1.0								
R <sub>p</sub> (Equipment or component response modification factor) =2.5								
$\Omega_0$ (System overstrength factor) = $2.0$								
I <sub>p</sub> (Importance factor) = 1.5								
z/h (Height factor ratio) = 1 (S <sub>DS</sub> =1.00g); 0 (S <sub>DS</sub> = 1.43g)								
Equipment or Component Natural Frequencies (Hz) = See Attachment A								
Overall dimensions and weight (or range thereof) = See Attachment A								
Equipment or Components @ grade designed in accordance with ASCE 7-10 Chapter 15:   Yes  No								
Design Basis of Equipment or Components (V/W) =								
S <sub>DS</sub> (Design spectral response acceleration at short period, g) =								
S <sub>D1</sub> (Design spectral response acceleration at 1 second period, g) =								
R (Response modification coefficient ) = OSP-0571-10								
$\Omega_0$ (System overstrength factor) =								
C <sub>d</sub> (Deflection amplification factor) = BY:Ali Sumer								
I <sub>P</sub> (Importance factor) = 1.5								
Height to Center of Gravity above base =								
Equipment or Component Natural Frequencies (Hz) =								
Overall dimensions and weight (or range thereof) =								
Tank(s) designed in accordance with ASME BPVC, 2015: ☐ Yes ☑ No								
List of Attachments Supporting Special Seismic Certification								
☐ Test Report(s) ☐ Drawings ☐ Calculations ☐ Manufacturer's Catalog								
☐ Other(s) (Please Specify): Attachment A								
OSHPD Approval (For Office Use Only) – Approval Expires on December 31, 2022								
Signature: Date: March 19, 2019								
Print Name: Ali Sumer Title: DSE								
Special Seismic Certification Valid Up to : S <sub>DS</sub> (g) = <u>See Above</u> z/h = <u>See Above</u>								
Condition of Approval (if applicable):								

"Access to Safe, Quality Healthcare Environments that Meet California's Diverse and Dynamic Needs"





Page 3 of 3

# SPECIAL SEISMIC CERTIFICATION CERTIFIED COMPONENT MATRIX

### **TRU PROJECT NO. 18000143**



Manufacturer: Vertiv Corporation

Model Line: EXL S1 UPS

TABLE 1

**Certified Product Construction Summary:** 

Carbon Steel Cabinets

### **Certified Options Summary:**

I/O Cabinets are customizable with the following options: Back Feed Disconnect (BFD), Sharing Inductor, or Common Mode Choke. I/O-1 is fitted with one of the options. I/O-2 is fitted with a combination of two of the options. I/O-3 is fitted with all three options.

### Mounting Configuration:

Base mounted - rigid

Note: Installed mounting configuration must be of similar configuration and equivalent strength and stiffness to those tested.

**Building Code: CBC 2016** 

Seismic Certification Limits:

 $S_{DS} = 1.00 g$  z/h=1.0  $S_{DS} = 1.43 g$  z/h=0.0

/<sub>P</sub>= 1.5

Model Line	Manual A	Dimensions (in)			Weight	Ž. Natas	
	Model 🛱	Depth	Width	Height	(lb)	Notes	UUT
	625 kVA/k <mark>W UP</mark> S	38.86	55.17	79	2902	(23	Extrap.
EXL S1 UPS	750 kVA/k <mark>W UP</mark> S	38.86	55.17	ım <del>7</del> 9r	2902	0	Extrap.
	800 kVA/k <mark>W UPS</mark>	38.86	55.17	79	2902	10	1
	1000 kVA/kW UPS	38.86	0 73.92 0	/2 <b>79</b> _9	4667	7	Interp.
	1100 kVA/kW UPS	38.86	73.9	79	4667		Interp.
	1200 kVA/kW UPS	38.86	73.9	79	4667		2
EXL Input/Output Cabinet	1	38.86	23.67	79	449	Back Feed Disconnect (BFD)	1
	I/O-1	38.86	23.67	ING 79	619	Sharing Inductor	Interp.
		38.86	23.67	79	978	Common Mode Choke	Interp.
		38.86	54.22	79	749	BFD, Sharing Inductor	Interp.
	1/0-2	38.86	54.22	79	1287	Sharing Inductor, Common Mode Choke	Interp.
		38.86	54.22	79	1648	BFD, Common Mode Choke	Interp.
	1/0-3	38.86	54.22	79	2266	BFD, Sharing Inductor, Common Mode Choke	2

Note: Model number identifies unique configuration

# UNIT UNDER TEST (UUT) SUMMARY SHEET





Manufactu Model Line	•					
UUT	Unit Description	Report Number	Testing Laboratory	1.00 1.43 1.00 1.43	z/h 1.0 0.0 1.0 0.0	1.50
1	EXL 800 kVA UPS with I/O-1	18000143-TP-001 R1	Pacific Earthquake Engineering Research Center			
2	EXL 1200 kVA UPS with I/O-3	18000143-TP-001 R1	Pacific Earthquake Engineering Research Center			
		ED CODE	COMP			
	RH KA	OSP-0571-10	FACE			
	OCAL	BY:Ali Sume:				
		RAVIA BUILDING	COLÉ			
		OTTDIM				
Notes:						

TRU Compliance, by Structural Integrity Associates, Inc. 844-TRU-0200 | info@trucompliance.com

## **UNIT UNDER TEST (UUT) SUMMARY SHEET**

## **TRU PROJECT NO. 18000143**



**UUT 1** 

Manufacturer: **Vertiv Corporation** Model Line: EXL S1 UPS

> 52SA800ANCAA86A **Serial Number:** D18AA60000

**Product Construction Summary:** 

NEMA 1 Enclosure

Model Number:

#### Options/Subcomponent Summary:

800 kVA UPS with I/O-1. Tested with the following option: Back feed disconnect (BFD)

**UUT Properties** 

**Dimension (in)** Weight Lowest Natural Frequency (Hz) (lb) Side-Side Vertical Depth Width Height Front-Back 3,351 39 79 79 10.92 9.78 6.70

**UUT Highest Passed Seismic Run Information** 

Building Code	Test Criteria	S <sub>DS</sub> (g)	z/h	l <sub>p</sub>	A <sub>FLX-H</sub> (g)	A <sub>RIG-H</sub> (g)	A <sub>FLX-V</sub> (g)	A <sub>RIG-V</sub> (g)
CBC 2016	ICC-ES AC156 03/2	1.00	1.0	1.5	1.60	1.20	0.95	0.38
		0 1.43 1	9 0.0	1:5/				

### Test Mounting Details:



UUT 1 is base mounted-rigid to the shake table with twelve (12) manufacturer supplied angles (P/N 544556P1) and twelve (12) 3/4" Grade 8 Bolts, lock washer, and flat washer.

Unit maintained structural integrity and remained functional per manufacturer requirement after shake table test. Contents were included in testing per operating conditions.

## UNIT UNDER TEST (UUT) SUMMARY SHEET

## **TRU PROJECT NO. 18000143**



UUT 2

Manufacturer: Vertiv Corporation
Model Line: EXL S1 UPS

**Product Construction Summary:** 

NEMA 1 Enclosure

Model Number:

#### Options/Subcomponent Summary:

1200 kVA UPS with I/O-3. Tested with the following options: Back feed disconnect (BFD), Bypass (Sharing) Inductors, and Common Mode Choke.

**UUT Properties Dimension (in)** Weight Lowest Natural Frequency (Hz) (lb) Side-Side Vertical Depth Width Height Front-Back 6,933 128 79 8.49 6.71 28.66 **UUT Highest Passed Seismic Run Information** Test Criteria **Building Code**  $S_{DS}(g)$ z/h I<sub>P</sub>  $A_{FLX-H}(g) | A_{RIG-H}(g) | A_{FLX-V}(g) | A_{RIG-V}(g)$ 1.00 1.0 1.5 1.60 0.95 CBC 2016 1.20 0.38 ICC-ES AC156

1.43

0.0

1.5

### Test Mounting Details:



UUT 2 is base mounted-rigid to the shake table with sixteen (16) manufacturer supplied angles (P/N 544556P1) and sixteen (16) 3/4" Grade 8 Bolts, lock washer, and flat washer.

Unit maintained structural integrity and remained functional per manufacturer requirement after shake table test. Contents were included in testing per operating conditions.