APPLICATION FOR OSHPD SPECIAL SEISMIC	OFFICE USE ONLY		
CERTIFICATION PREAPPROVAL (OSP)	APPLICATION #: OSP - 0580 - 10		
OSHPD Special Seismic Certification Preapproval (OSP)			
Type: ⊠ New □ Renewal			
Manufacturer Information			
Manufacturer: Advanced Cooling Technologies, Inc.			
Manufacturer's Technical Representative: <u>Tim True</u>			
Mailing Address: 3127 Independence Drive, Livermore, CA 94551			
Telephone: 925.918.0767 Email: tim.true	e@advancedcoolingtech.com		
Product Information FOR CODE C	Olo		
Product Name: Airsys Medicool Air-Cooled Chillers			
Product Type: Air-Cooled Chiller	T.		
Product Model Number: See Attachment 1 (List all unique product identification numbers and/or part numbers)	CF		
General Description: Carbon steel air-cooled chillers. Seismic enhal	ncements made to the test units shall be		
incorporated into the production units.			
Mounting Description: Rigid floor mounted and isolated floor mounted	d on neoprene pads.		
Applicant Information	CODE		
Applicant Company Name: Manwill Engineering LLC ILD INC			
Contact Person: Derek Manwill, SE			
Mailing Address: PO Box 1194, Bend, OR 97709			
Telephone: 541.241.2102 Email: derek@	@manwillSE.com		
I hereby agree to reimburse the Office of Statewide Health Faccordance with the California Administrative Code, 2016.	Planning and Development review fees in		
Signature of Applicant:	Date:10/15/2018		
Title: President Company Name: Manwi	ill Engineering LLC		

"Access to Safe, Quality Healthcare Environments that Meet California's Diverse and Dynamic Needs"





Page 1 of 3

California Licensed Structural Engineer Responsible for the Engineering and Test Report(s)
Company Name: Manwill Engineering LLC
Name: Derek Manwill, SE California License Number: S6266
Mailing Address: PO Box 1194, Bend, OR 97709
Telephone: 541.241.2102 Email: derek@manwillSE.com
Supports and Attachments Preapproval
Supports and attachments are preapproved under OPM- (Separate application for OSHPD Preapproval of Manufacturer's Certification (OPM) of Supports and attachments is required)
Supports and attachments are not preapproved
Certification Method
 ✓ Testing in accordance with: ✓ Other (Please Specify):
BY:Ali Sumer
Testing Laboratory DATE: 02/26/2019
Company Name: Environmental Testing Laboratory
Contact Name: Jeremy Lange
Mailing Address: 11034 Indian Trail, Dallas, TX 75229
Telephone: 972.247.9657 Email: jeremy@etldallas.com



Page 2 of 6



OFFICE OF STATEWIDE HEALTH PLANNING AND DEVELOPMENT FACILITIES DEVELOPMENT DIVISION

Seismic Parameters
Design in accordance with ASCE 7-10 Chapter 13: ⊠ Yes □ No
Design Basis of Equipment or Components $(F_p/W_p) = Rigid:1.5$, Iso.:3.6 $(S_{DS} = 2.0g)$; Rigid:1.13, Iso.:1.5 $(S_{DS} = 2.5g)$
S_{DS} (Design spectral response acceleration at short period, g) = $2.0 (z/h = 1)$; $2.5 (z/h = 0)$
a _p (In-structure equipment or component amplification factor) = 2.5
R _p (Equipment or component response modification factor) = 6.0 (rigid); 2.5 (neoprene isolated)
Ω_0 (System overstrength factor) =2.0
I _p (Importance factor) = 1.5
z/h (Height factor ratio) = $1 (S_{DS} = 2.0g)$; $0 (S_{DS} = 2.5g)$
Equipment or Component Natural Frequencies (Hz) = See Attachment 2
Overall dimensions and weight (or range thereof) = See Attachments 1 & 2
Equipment or Components @ grade designed in accordance with ASCE 7-10 Chapter 15: Yes No
Design Basis of Equipment or Components (V/W) =
S _{DS} (Design spectral response acceleration at short period, g) =
S _{D1} (Design spectral response acceleration at 1 second period, g) =
R (Response modification coefficient) = OSP-0580-10
Ω_0 (System overstrength factor) =
C _d (Deflection amplification factor) = BY:Ali Sumer
I _P (Importance factor) = 1.5
Height to Center of Gravity above base =
Equipment or Component Natural Frequencies (Hz) =
Overall dimensions and weight (or range thereof) =
Tank(s) designed in accordance with ASME BPVC, 2015: ☐ Yes ☐ No
List of Attachments Supporting Special Seismic Certification
Other(s) (Please Specify): Attachments 1 & 2
OSHPD Approval (For Office Use Only) – Approval Expires on December 31, 2022
Signature. A February 22, 2040
Signature: Date: February 22, 2019
Print Name: Ali Sumer Title: DSE Special Seismic Certification Valid Up to: S _{DS} (g) = See Above z/h = See Above
Condition of Approval (if applicable):

"Access to Safe, Quality Healthcare Environments that Meet California's Diverse and Dynamic Needs"





Page 3 of 3



ADVANCED COOLING TECHNOLOGIES

ATTACHMENT 1: CERTIFIED COMPONENTS

SEISMIC COMPLIANCE REPORT

DOCUMENT NO.: 18042CR1.0

TABLE 1 - RIGID

MANUFACTURER: ADVANCED COOLING TECHNOLOGIES, INC.

PRODUCT FAMILY: AIRSYS MEDICOOL CHILLERS DIMENSIONS (in) MAX. WT. DECENTION (100)							
MODEL NUMBER		DEPTH	WIDTH	HEIGHT	(lb)	DESCRIPTION / NOTES	BASIS
Airsys Medico	Airsys Medicool Air-Cooled Chillers						
MEDICOOL/CH	10E1P4R407.M.GEH	55.5	25.2	65.0	640	10kW	UUT 1
MOUNTING:	Rigid floor mounted.				SEISMIC LEVELS:	$S_{DS} = 2.0g$ for z/h = 1 $S_{DS} = 2.5g$ for z/h = 0	I _P = 1.5
NOTES:	Product Construction: Carbon steel construction. 480V, 3ph, 60Hz. Options/Subcomponents: Model number uniquely identifies subcomponents, materials, construction, and configuration. There are no options or variations.						

TABLE 2 - ISOLATED

PRODUCT	FAMILY: AIRSYS	MEDICOOL	CHILLERS	D		
MODEL NU	MBER	DEPTH	MENSIONS (in)	MAX. WT.	DESCRIPTION / NOTES	BASIS
Airsys Medic	ool Air-Cooled Chi	llers		AAXXXXXXXXXX	(I) LEI	
MEDICOOL/CH	55E4P4R410A.M	79.9	D 55.1√ 7 4 78.3	_2130	55kW	UUT 2
MEDICOOL/CH	70E4P4R410.M	111.4	40.9 75.2	2920	70kW	UUT 3
MOUNTING:	Isolated floor mount	ed <mark>on neo</mark> prene	pads.	SEISMIC LEVELS:	$S_{DS} = 2.0g \text{ for z/h} = 1$ $S_{DS} = 2.5g \text{ for z/h} = 0$	I _P = 1.5
NOTES:		nents: Model	eel construction. 480V, 3p number uniquely identifies		nts, materials, construction, and conf	guration. There

derek@manwillSE.com 541.241.2102 www.manwillSE.com

02/26/2019 OSP-0580-10 Page 4 of 6



ADVANCED COOLING TECHNOLOGIES

ATTACHMENT 2: UNIT UNDER TEST SUMMARIES

SEISMIC COMPLIANCE REPORT

UUT 1 - 10kW

DOCUMENT NO.: 18042CR1.0

MANUFAC	TURER:	ADVANCED COOLING TECHNOLOGIES, INC.				
MODEL NU	JMBER:	MEDICOC	L/CH10E1P4	R407.M.	GEH	
UNIT FUNC	CTION:	CHILLER				
SERIAL NU	JMBER:	F3021804	0069			
DIN	/IENSIONS	(in)	WEIGHT	RES	. FREC	Q. (Hz)
DEPTH	WIDTH	HEIGHT	(lb)	F-B	S-S	V
55.5	25.2	65.0	640	10.0	8.9	>33
BUILDIN	BUILDING CODE		RITERIA	LAB	REPO	RT NO.
2016	2016 CBC		AC156	ET	L 18042	2TR1
S _{DS} (g)	z/h	A _{FLX-H} (g)	A _{RIG-H} (g)	A _{FLX-V}	(g) A	N _{RIG-V} (g)
2.0	1	3.20	2.40	1.68	,	0.68
2.5	0	3.20	2.40	1.00	'	0.00

IMPORTANCE FACTOR, $I_P = 1.5$

Unit was full of operating content during the shake table test. Unit maintained structural integrity and remained functional per manufacturer requirement after shake table test.

MOUNTING:	Rigid floor mounted using (6) 5/16" Grade 8 bolts with clipped washers.		
CONSTRUCTION:	Carbon steel construction.		
SUBCOMPONENTS:	Subcomponents are uniquely identified by the model number.		
TESTING NOTES:	N/A S OGD OF SO 10		

UUT 2 - 55kW

MANUFAC	TURER:	ADVANCED COOLING TECHNOLOGIES, INC.				
MODEL NU	JMBER:	MEDICOC	L/CH <mark>5</mark> 5E4P4	R410A.M	7 1 1	_ Dun
UNIT FUNC	CTION:	CHILLER	NXXXXXX			
SERIAL NU	JMBER:	F3021705	0116	DATE	: 0	2/26/2
DIN	/IENSIONS	(in)	WEIGHT	RES.	FRE	Q. (Hz)
DEPTH	WIDTH	HEIGHT	(lb)	F-B	S-S	V
79.9	55.1	78.3	2130	6.2	8.5	16.9
BUILDING CODE		TEST C	RITERIA	LAB	REPO	ORT NO.
2016	CBC	ICC-ES AC156		/ ETL	ETL 18042TR1	
S _{DS} (g)	z/h	A _{FLX-H} (g)	A _{RIG-H} (g)	A _{FLX-V} (g),,	A _{RIG-V} (g)
2.0	1	3.20	2.40	1.68	90	0.68
2.5	0	3.20	2.40	1.00		0.00

IMPORTANCE FACTOR, $I_P = 1.5$

Unit was full of operating content during the shake table test. Unit maintained structural integrity and remained functional per manufacturer requirement after shake table test.

requirement after snake	rable test.
MOUNTING:	Isolated floor mounted on (6) 4"x4"x0.75" neoprene pads using (6) 5/8" Grade 8 bolts.
CONSTRUCTION:	Carbon steel construction.
SUBCOMPONENTS:	Subcomponents are uniquely identified by the model number.
TESTING NOTES:	#14x1.5" Buildex Teks screws were added to secure the panels. Nothing was done to the back mesh panels. The two full height front panels each received (7) screws: (3) along each side (1in from top, middle, 3in from bottom; all 0.75in from the side) and (1) in the middle top (1in from top). The two side panels each received (10) screws: (3) along each side (1in from top, middle, 3in from bottom; all 0.75in from the side) and (2) in the top and bottom (1in from top/bottom at third points). The electrical enclosure door received (2) screws: top right and bottom right corners (1in from top/bottom, 0.75in from side). The panel below the electrical enclosure door received (4) screws: each corner (1in from top/bottom, 0.75in from side).

derek@manwillSE.com 541.241.2102 www.manwillSE.com

02/26/2019 OSP-0580-10 Page 5 of 6



ADVANCED COOLING TECHNOLOGIES

ATTACHMENT 2: UNIT UNDER TEST SUMMARIES

SEISMIC COMPLIANCE REPORT

UUT 3 - 70kW

DOCUMENT NO.: 18042CR1.0

MANUFAC	TURER:	ADVANCED COOLING TECHNOLOGIES, INC.				
MODEL NU	JMBER:	MEDICOC	L/CH70E4P4	R410.M		
UNIT FUNC	CTION:	CHILLER				
SERIAL NU	JMBER:	F3021804	0098			
DIN	IENSIONS	(in)	WEIGHT	RES.	FREQ	. (Hz)
DEPTH	WIDTH	HEIGHT	(lb)	F-B	S-S	V
111.4	40.9	75.2	2920	7.4	8.9	22.9
BUILDIN	BUILDING CODE		RITERIA	LAB F	REPOR	T NO.
2016	CBC	ICC-ES	AC156	ETL	_ 18042 [·]	TR1
S _{DS} (g)	z/h	A _{FLX-H} (g)	A _{RIG-H} (g)	A _{FLX-V} ((g) A _ı	_{RIG-V} (g)
2.0	1	3.20	2.40	1.68		0.68
2.5	0	3.20	2.40	1.00		0.00

IMPORTANCE FACTOR, I_P = 1.5

Unit was full of operating content during the shake table test. Unit maintained structural integrity and remained functional per manufacturer prequirement after shake table test.

375000.	1005-3	. =
1222	m e	
	•	
	1	
$C_{\Theta_{\lambda}}$		اان

MOUNTING:	Isolated floor mounted on (6) 4"x4"x0.75" neoprene pads using (6) 5/8" Grade 8 bolts.
CONSTRUCTION:	Carbon steel construction.
SUBCOMPONENTS:	Subcomponents are uniquely identified by the model number.
TESTING NOTES:	#14x1.5" Buildex Teks screws were added to secure the panels. Nothing was done to the back mesh panels. The two side panels and the three full height front panels each received (7) screws: (3) along each side (1in from top, middle, 3in from bottom; all 0.75in from the side) and (1) in the middle top (1in from top). The electrical enclosure door received (2) screws: top right and bottom right corners (1in from top/bottom, 0.75in from side). The panel below the electrical enclosure door received (4) screws: each corner (1in from top/bottom, 0.75in from side).



derek@manwillSE.com 541.241.2102 www.manwillSE.com

02/26/2019 OSP-0580-10 Page 6 of 6